

Work Order Report

Work Order:

RFP-Removal and Installation of the Roof on the Tobacco Root Mountains Care Center and Storage Building located at, 326 Madison, Sheridan, MT 59749

Contractor:

Contact: David Reintsma, Facility Director

326 Madison Street

P O Box 308

Sheridan, MT, 59749

406-842-5600

Job Name: Madison County- Tobacco Root Mountains Care Center

Property: 326 Madison Street

Sheridan, MT 59749

Job Instructions:

RFP-Removal and Installation of the Roof on the Tobacco Root Mountains Care Center and Storage Building located at, 326 Madison, Sheridan, MT 59749

Bid/RFP Due Date:

Friday, September 4, 2020-5:00PM Local Time

Bid/RFP Status:

Open-accepting bids and proposals.

Tobacco Root Mountains Care Center, 326 Madison Street, P O Box 308, Sheridan, MT, 59749

Publicly Opened and read aloud on September 8, 2020, at 10:30AM Local Time at the Madison County Commissioners' meeting, 103 W. Wallace, PO Box 278, Virginia City, MT 59755

REQUEST FOR PROPOSALS:

Madison County is seeking bids and proposals from qualified contractors to remove existing roofing and furnish materials of like kind to complete the installation of a new-asphalt shingled roof, membrane roofing, metal roofing, guttering/downspouts and all other materials required to comply with Montana Building codes.

Scope of work:

The project consists of:

- Removal and debris disposal of all materials related to the removal of the existing roofing and guttering/downspouts on the Care Center and roofing on one (1) 20x20 storage located at the Tobacco Root Mountains Care Center, 326 Madison, Sheridan, MT 59749.
- Installation of new roofing and materials of like kind including; asphalt shingles, membrane roofing on a low-slope roof section, metal roofing on entranceways and guttering/downspouts on the Care Center and the installation of asphalt shingles on one (1) 20x20-storage building located on the grounds of the Tobacco Root Mountains Care Center, 326 Madison Street, Sheridan, MT 59749.

Contractor to provide all necessary materials, labor, debris disposal, and equipment necessary to complete the removal and the installation of a new roof on the Care Center and one (1) 20x20-storage building. Completed project must comply with the Montana Building Codes and comply with all manufacturer's installation guidelines for all materials used.

Contractor shall keep work area neat at the end of each workday and contained through the duration of the job.

| CLN | CLEANING | | | | |
|-------|------------|------|--|-----|-------------|
| CLN | PWASH | + | Clean with pressure/chemical spray | | |
| | | | 1,288.22 SF | _ = | [] |
| TOTAL | L CLEANING | | | = | |
| DMO | GENERAL DE | MOLI | ΓΙΟΝ | | |
| DMO | DUMP | - | Dumpster load - Approx. 20 yards, 4 tons of debris | | |
| | | | 2.00 EA | = | [] |
| DMO | X | _ | Exterior light fixture | | |
| | | | 4.00 EA | = | [] |
| DMO | RFD | _ | Roof drain - cast iron - 2" to 6" outlet | | |
| | | | 2.00 EA | = | [] |
| DMO | ARMV> | - | Tear off, haul and dispose of comp. shingles - Laminated 207.18 SQ | = | [] |
| DMO | FLCAP> | _ | Cap flashing - large | | |
| | | | 134.45 LF | = | [] |
| DMO | FLCRB | _ | Curb flashing - PVC/TPO | | |
| | | | 184.00 LF | = | [] |
| DMO | FLP60P | _ | Flash parapet wall only - PVC/TPO | | |
| | | | 364.09 LF | = | [] |
| DMO | FLTB | _ | Aluminum termination bar / flashing for membrane roofs | | |
| | | | 64.42 LF | = | [] |
| DMO | HIGH | _ | Additional charge for high roof (2 stories or greater) | | |
| | | | 27.58 SQ | = | [] |
| DMO | IF1 | _ | Insulation - fiberglass board, 1" | | |
| | | | 27.58 SQ | = | [] |
| DMO | ISO2 | _ | Insulation - ISO board, 2" | | |
| | | | 27.58 SQ | = | [] |
| DMO | MCANT | _ | Membrane roofing - cant strips - wood | | |
| | | | 291.28 LF | = | [] |

| DMO | MTL+ | - | Metal roofing - High grade | | |
|-------|----------------|-------|--|-----|----------|
| | | | 471.23 SF | = | _ [] |
| DMO | SPRMV+ | - | Tear off, haul and dispose membrane roofing - full adhered | | |
| | | | 39.23 SQ | = | _ [] |
| DMO | VENTG | - | Gravity roof ventilator - 18" | | |
| | | | 5.00 EA | = | _ [] |
| DMO | GUTA | - | Gutter / downspout - aluminum - up to 5" | | |
| | | | 1.00 LF | = | _ [] |
| DMO | GUTA> | - | Gutter / downspout - aluminum - 6" | | |
| | | | 118.50 LF | = | _ [] |
| TOTAI | L GENERAL DEN | MOLI | TION | = | |
| | | | | | |
| ELE | ELECTRICAL | | | | |
| ELE | TVRS | + | Television antenna - Detach & reset | | |
| | | | 1.00 EA | . = | _ [] |
| TOTAI | LELECTRICAL | | | = | |
| | | ~~~ | | | |
| ELS | ELECTRICAL - | SPEC | | | |
| ELS | DISHRS | + | Digital satellite system - Detach & reset | | r 1 |
| | | | 10.00 EA | = | _ [] |
| TOTAI | L ELECTRICAL . | - SPE | CIAL SYSTEMS | = | |
| EQU | HEAVY EQUIP | MEN | Γ | | |
| EQU | CRANE | + | Crane and operator - 14 ton capacity - 65' extension boom | | |
| | | | 10.00 HR | = | _ [] |
| EQU | TELEH | + | Telehandler/forklift and operator | | |
| | | | 40.00 HR | = | _ [] |
| TOTAI | L HEAVY EQUIP | MEN | T | = | |
| | | | | | <u> </u> |

FEE PERMITS AND FEES

| FEE | DEL | + | Delivery charge (Bid Item) | | |
|-------|----------------|-----|--|-----|-----|
| | | | 4.00 EA | _ = | [] |
| TOTAI | L PERMITS AND | FEE | S | = | |
| HVC | HEAT, VENT & | AIR | CONDITIONING | | |
| HVC | ACFINN> | + | Comb/straighten a/c cond. fins - w/out trip charge - Large 2.00 EA | = | [] |
| HVC | ACFINS> | + | Comb/straighten a/c cond. fins - w/trip charge - Large 1.00 EA | = | [] |
| HVC | LABL | + | HVAC - General Laborer - per hour 4.00 HR | = | [] |
| HVC | PACRS | + | Packaged air conditioning unit - Detach & reset 2.00 EA | = | [] |
| TOTAL | L HEAT, VENT & | AIR | CONDITIONING | = | |
| LAB | LABOR ONLY | | | | |
| LAB | LBR | + | General Laborer - per hour 75.00 HR | = | [] |
| LAB | SUPERC | + | Commercial Supervision / Project Management - per hour 75.00 HR | = | [] |
| TOTAL | L LABOR ONLY | | | = | |
| LIT | LIGHT FIXTUR | ES | | | |
| LIT | X | + | Exterior light fixture 4.00 EA | = | [] |
| TOTAL | L LIGHT FIXTUR | RES | | = | |
| PLM | PLUMBING | | | | |

| PLM | RFD | I | Roof drain - cast iron - 2" to 6" outlet | | |
|-------|------------|---|--|---------|-----|
| | | | 2.00 EA | = | [] |
| TOTAI | L PLUMBING | | | = | |
| | | | | | |
| PNT | PAINTING | | | | |
| PNT | LAB | + | Painter - per hour | | |
| | | | 2.00 HR | = | [] |
| PNT | X2 | + | Exterior - paint two coats | | |
| | | | 1,288.22 SF | = | [] |
| TOTAI | L PAINTING | | | = | |
| | | | | | |
| RFG | ROOFING | | | | |
| RFG | 300S | + | Laminated - comp. shingle rfg w/out felt | | |
| | | | 238.33 SQ | = | [] |
| RFG | ASTR- | + | Asphalt starter - universal starter course | | |
| | | | 668.67 LF | = | [] |
| RFG | DRIP | + | Drip edge | | |
| | | | 891.55 LF | = | [] |
| RFG | FELT15 | + | Roofing felt - 15 lb. | | |
| | | | 207.18 SQ | = | [] |
| RFG | FLCAP> | + | Cap flashing - large | | |
| | | | 134.45 LF | = | [] |
| RFG | FLCRB | + | Curb flashing - PVC/TPO | | |
| | | | 184.00 LF | = | [] |
| RFG | FLP60P | + | Flash parapet wall only - PVC/TPO | | |
| | | | 364.09 LF | = | [|
| RFG | FLPIPE | + | Flashing - pipe jack | | |
| | | | 12.00 EA | = | [] |
| RFG | FLTB | + | Aluminum termination bar / flashing for membrane | e roofs | |
| | | | 64 42 LE | _ | r ı |

| RFG | HIGH | + | Additional charge for high roof (2 stories or greater) 27.58 SQ | = | [] |
|-----|--------|---|--|---|-----|
| RFG | IF1 | + | Insulation - fiberglass board, 1" 27.58 SQ | = | [] |
| RFG | ISO2 | + | Insulation - ISO board, 2" 27.58 SQ | = | [] |
| RFG | ISO3 | + | Insulation - ISO board, 3" 0.00 SQ | = | [] |
| RFG | IWS | + | Ice & water barrier 0.00 SF | = | [] |
| RFG | MCANT | + | Membrane roofing - cant strips - wood 291.28 LF | = | [] |
| RFG | MTL+ | + | Metal roofing - High grade 471.23 SF | = | [] |
| RFG | MTLGT+ | + | Gable trim for metal roofing - 26 gauge 52.00 LF | = | [] |
| RFG | RENAIL | + | Re-nailing of roof sheathing - complete re-nail 0.00 SF | = | [] |
| RFG | RIDGC+ | + | Ridge cap - High profile - composition shingles 675.71 LF | = | [] |
| RFG | RIDGM | + | Ridge cap - metal roofing 24.25 LF | = | [] |
| RFG | SPLY | + | Single ply membrane - Mechanically attached - 45 mil 39.23 SQ | = | [] |
| RFG | STEP | + | Step flashing 51.00 LF | = | [] |
| RFG | VENTB | + | Roof vent - turbine type 2.00 EA | = | [] |
| RFG | VENTE | + | Exhaust cap - through roof - 6" to 8" 4.00 EA | = | [] |
| RFG | VENTE< | + | Exhaust cap - through roof - up to 4" 21.00 EA | = | [] |

| RFG | VENTG | + Gravity roof ventilator - 18" | | |
|-------|-------------|--|---|-----|
| | | 5.00 EA | = | [] |
| RFG | VENTR | + Continuous ridge vent - shingle-over style | | |
| | | 341.30 LF | = | [] |
| RFG | VENTT | + Roof vent - turtle type - Metal | | |
| | | 2.00 EA | = | [] |
| RFG | VMTLW | + Valley metal - (W) profile | | |
| | | 258.70 LF | = | [] |
| TOTAL | ROOFING | | = | |
| SFG | SOFFIT, FAS | SCIA, & GUTTER | | |
| SFG | GUTA | + Gutter / downspout - aluminum - up to 5" | | |
| | | 1.00 LF | = | [] |
| SFG | GUTA> | + Gutter / downspout - aluminum - 6" | | |
| | | 118.50 LF | = | [] |
| TOTAL | SOFFIT, FAS | SCIA, & GUTTER | = | |
| TMP | TEMPORARY | Y REPAIRS | | |
| TMP | TLT | + Temporary toilet (per month) | | |
| | | 1.00 MO | = | [] |
| TOTAL | TEMPORAR | RY REPAIRS | = | |
| | | | | |

| Subtotal fo | or Non | O&P Items: | |
|-------------|---------|------------|--|
| Subto | tal for | O&P Items: | |
| | Labor | Minimums: | |
| Overhead | @ | % = | |
| Profit | @ | % = | |
| | | Total Tax: | |
| | | | |
| | | Total Bid: | |

| THIS BID IS GOOD FOR | DAYS FROM THE DATE SUBMITTED. |
|-----------------------------|-------------------------------|
| RESPECTFULLY SUBMITTED THIS | DAY OF |
| | BY |
| TI | TLE |
| | ANY |
| | ESS |
| | |
| | |
| PHO | ONE |
| CONTRACTOR'S LICEN | ISE# |
| REFERENCES (TWO OR MO | ORE PLEASE): |

08.20.20